

SUBJECT : BILL OF QUANTITIES

BILL NO 2 : SPRINKLER SYSTEM

Item	Description	Unit	Quantity	Tariff	Amount
1	All in accordance with the drawings and specification SPRINKLER SYSTEM Price given below shall be nett cost of equipment and materials supplied and installed on site and shall: a) - exclude profit, overheads, financing, insurance and guarantee costs b) - exclude engineering and management costs c) - exclude VAT				
1.1	Direct Reading Flow Meter Allow for welding socket on infill line to tanks and installing meter	No	1		
1.2	Pump Room Sprinklers replace existing pump room sprinkler heads with new 141 ° C	No	38		
1.3	Sprinklers in staircases underneath stairs Replace old type sprinkler heads with new 68° C quick response sprinkler heads	No	38		
1.4	Sprinklers in delivery area Block A Replace old type sprinkler heads with new 68° C quick response sprinkler heads	No	4		
1.5	Sprinklers in Block A Printing Room Replace old type sprinkler heads with new 68° C quick response sprinkler heads	No	12		
1.6	Floor piping and heads based on new range pipes connected to existing main, allow for 3.6 meter piping per sprinkler head and upgrade of sprinkler range plus all fittings hangers and supports, as shown on the detailed drawing (Based on cost per head) Block A Server room office Cleaners office Stationary Office Stationary Store Meeting room	No No No No No	3 5 2 2 1		
1.7	Allow for plugging and blanking of existing sprinklers in nerve centre	No	5		
1.8	Allow for drain and refill per floor per block.	No	5		
1.9	Any item not listed above, Specify				
TOTAL TRANSFERRED TO "SUMMARY OF TENDER BILLS" ITEM 2					